



15-009-03172-0000

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
EUST. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 2 1965
03-02-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. G. R. Moore of Nat'l. Coop. Ref. Assoc. has this date requested permission to plug the following described well:

Mr. Donald I. Lawless guarantees payment of the plugging fee.

Operator's full Name: National Coop. Refinery Association

Complete Address: 1417 Wichita Plaza, Wichita, Kansas

Lease Name: Joseph Well No. # 1

Location: NE SW NW Sec. 32 Twp. 16 Rge. 11 (E) (W) W

County Barton Total Depth 3377 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. D. B. Pulley was instructed to plug the well as follows:

10" 777' Cwc. 5 1/2" 3370'.

Sanded hole back to 300' & dumped 5 sax cement with
dump bailer. Pulled pipe. Mudded hole to 350'; set rock
bridge; displaced 25 sax cement. Mud to 30'; set rock
bridge & displaced 12 sax cement, cementing to base of
cellar.

Very truly yours,

Don Truman
Conservation Division Agent