



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 10 1962
11-19-62
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Jack Haynes of Bennett & Roberts Oil Op. has this date requested permission to plug the following described well:

Mr. D. L. Roberts guarantees payment of the plugging fee.

Operator's full Name: Bennett & Roberts Oil Operations

Complete Address: Drawer 633, Russell, Kansas

Lease Name: Hitschmann "C" Well No. 3

Location: NE SE SE Sec. 32 Twp. 16 Rge. 11 (E) (W)

County Barton Total Depth 3322 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Albert Unruh was instructed to plug the well as follows:

8 5/8" 301' Cwc.

Sand hole back to 3300' & dump 4 sax cement with dump

bailer. Pull pipe. Mud hole to 280', set over night plug.

Bail hole dry; displaced 25 sax cement; mud to 40', set

10' rock bridge, & 10 sax cement, cement to base of
cellar.

Very truly yours,

Don Unruh
Conservation Division Agent