

State of Kansas



15-167-03007-0000

State Corporation Commission

CONSERVATION DIVISION

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
OCT 17 1965
10-17-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Morton Specter of Specter Pipe & Supply, Inc. has this date requested permission to plug the following described well:

Mr. Morton Specter guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply, Inc.

Complete Address: Box 169, Russell, Kansas

Lease Name: Harbaugh Well No. # 1

Location: SW SW SW Sec. 25 Twp. 14 Rge. 15 (E)(W) W

County Russell Total Depth 3203 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ralph Lynch was instructed to plug the well as follows:

8 5/8" 816' Cwc.

Sanded hole back to 2900' & dumped 5 sax cement with dump bailer.

Pulled pipe. Mudded hole to 320', set 20' rock bridge, & displaced

4 yds. ready-mix cement, cementing from 300' to base of cellar.

Very truly yours,

Don Truman
Conservation Division Agent