



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 19 1965

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

CONSERVATION DIVISION
Wichita, Kansas

4-19-1965

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Hoberecht of Birmingham-Bartlett Drilling Co.

date requested permission to plug the following described well:

Mr. Hoberecht guarantees payment of the plugging fee.

Operator's full Name: Birmingham-Bartlett Drilling Co.

Complete Address: 300 Kaufman Bldg. Wichita, Kansas

Lease Name: Jensen Well No. # 1

Location: SE SE Sec. 26 Twp. 22 Rge. 23 (E/W)

County Hodgeman Total Depth 4509' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hoberecht was instructed to plug the well as follows:

8 5/8"-240' Circulated w/cement. 5 1/2"-4504' Cemented.

Plug bottom w/5 sax.cement top cement 4450'. Mud 4450' to 700'

Spotted 25 sax.cement 700' to 625' Mud 625' to 250'

Spotted 25 Sax.cement 250' to 175' Mud 175' to 45'

Plug, Hulls, 15 sax.cement 45' to 0

Very truly yours,

Hugh Scott
Conservation Division Agent