

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION 21E-21E-21E

SEC. 34 TWP. 22 RGE. 16-W

Dry Hole _____ Abandoned Oil Well _____ Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No. 1 Lease Kachelman Kachelman

Operator J. M. Huber - Co. Inc. Address Box #460 - Pratt - Kans.

Field _____ County Rawl

Total Depth 4060 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 1/2" - 720 ft. Circulated with cement
5 1/2" casing set at 4060 ft. Cemented with 15 sacks cement
Plugged back to 3650 with Lam Wells Plug & chat.
Mixed 5 sacks of cement at 3650 ft. Shot of a
pulled the 5 1/2" casing - Filled with mud to 2950
Set Rock Bridge & 15 sacks of cement at 2950 ft.
Mud to 36 ft. Plug & 10 sacks of cement
at the surface*

RECEIVED
STATE CORPORATION COMMISSION

FEB 20 1951

2-20-51

CONSERVATION DIVISION
Wichita, Kansas

C. P. Stough
District Conservation Agent

Date 2-18-51

PLUGGING
FILE NO. 34 TWP. R. 16W
BOOK PAGE 63 LINE 6

f