

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-083-20887-00.00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Energy Methods Corporation

Complete Address 2850 Security Life Bldg, 1616 Glenplace, Denver, Colo. 80202

Lease Name Smidt Well-No. #1-8

Location Center of SW/NE Sec. 8 Twp. 21 Rge. 25 (East) (West)

County Hodgeman Total Depth 4550'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling, Inc.

Address P. O. Box 1586, Great Bend, Ks. 67530 License No. _____

Operation Completed: Hour: 1:25PM. Day: 29th Month: Oct. Year: 19 81

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8"-328' s.p. cuc. w/240 sacks common-2% Gel.-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

1st plug @ 810' w/70 sacks cement

2nd plug @ 330' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

5 sacks of cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

NOV 2 1981

INVOICED

DATE 11-17-81

INV. NO. 8334-W

I hereby certify that the above plugging instructions were given as stated.
Signed: Arthur G. Club
Conservation Division Agent

CONSERVATION DIVISION
Wichita, Kansas