

15.083.20296.00.00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 28 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Petroleum Inc.

Complete Address R.R. 2, Great Bend, Kansas 67530

Lease Name Vieux "D" Well No. 2

Location App C SW SE Sec. 14 Twp. 21 Rge. 25 (E) (W)

County Hodgeman Total Depth 4511

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Glenn Pipe Pulling

Address Ellinwood, Kansas License No. 396

Operation Completed: Hour 10:00AM Day 24 Month 8 Year 1973

The above well was plugged as follows:

8 5/8" to 404' circulated w/ cement. 5 1/2" casing to 4502' cemented.

Top perforations 4480' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4410' Mud 4410' to 450'

Spotted 50 sacks cement 450' to 300' Mud 300' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Go Pump

Pulled 3500' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

DATE 8/30/73

INV. NO. 7838-4

Signed: [Signature]
Well Plugging Supervisor