

15.083.10308.00.00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1963
10-7-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Schultz, Turner & Webb

Complete Address: 1940 Mercantile Dallas Bldg. Dallas, Texas

Lease Name Ewy Well No. A-2

Location C SW SE Sec. 17 Twp. 22 Rge. 22 (Ø) (W)

County Hodgeman Total Depth 4536'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Chase, Kansas License No. 436

Operation Completed: Hour 7 Pm Day 2 Month 10 Year 63

The Above well was plugged as follows:

8 5/8"-296' Circulated w/200 Sax.cement. 4 1/2"-4534' Cemented w/150 Sax.cement.
Perforations 4474' to 4484' Hole plug w/packer and tubing top tubing at 4320'
Dump 5 Sax.cement 4320' to 4260' Mud 4260' to 700'
25 Sax.cement spotted at 700' Mud top cement to 275'
25 Sax.cement spotted 275' to 200' Mud 200' to 50'
10' rock bridge 50' to 40' 15 Sax.cement 40' to surface.
Weld cap on surface. Company pump. Bulled 3471' 4 1/2" pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 10/9/63
INV. NO. 4843-11