

KANSAS

15.083.20076.00.00
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1973

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Braden- Deem Inc.

Complete Address 200 E. 1st, Wichita, Kansas

Lease Name E. Öppy Well No. 4

Location NW NE Sec. 19 Twp. 22 Rge. 22 XY (E) (W)

County Hodgeman Total Depth 4572'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Knights Casing Pulling

Address Chase, Kansas License No. 624

Operation Completed: Hour 10:00AM Day 21 Month 2 Year 1973

The above well was plugged as follows:

8 5/8" to 224' circulated w/ cement. 5 1/2" to 4548' cemented.

Open hloe 4548' to 4572' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4490' Mud 4490' to 700'

Spotted 70 sacks cement 700' to 400' Mud 400' to 200'

Plug& 50 sacks cement 200' to 0'. Allied Pump Truck

Pulled 2446' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edmond J. Eells
Well Plugging Supervisor

INVOICED

DATE 2/28/73
INV. NO. 7048-W