

15.083.10109.00.00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 8 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Imperial Oil Of Kansas

Complete Address: Box 97 Wakeeney, Kansas

Lease Name Hertel Well No. # 2

Location C SE SW Sec. 26 Twp. 22 Rge. 22 (E) (W)

County Hodgeman Total Depth 4510'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Inc.

Address: Great Bend, Kansas License No. # 399

Operation Completed: Hour 4 PM Day 5 Month 7 Year 63

The Above well was plugged as follows:

8 5/8"-239' Circulated w/cement. 5 1/2"-4509' Cemented. Plug back to 4432'

Perforations 4420' to 4426'

Plug bottom w/sand 4432' to 4400' 5 Sax. cement 4400' to 4360'

Mixed heavy mud, pump down pipe 4360' to 600' Pump 200 Sax. cement 600' to surface

Pulled 2412' 5 1/2" pipe. Weld cap on surface. Halliburton Cem. Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 7/8/63

INV. NO. 7262-W