


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission  
111 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Pawnee County, Sec. 1 Twp. 22 Rge. 16 (E) (W)  
Location as "NE/CNWSW" or footage from lines NW NW NW  
Lease Owner Mull Drilling Company, Inc.  
Lease Name Malin Well No. 2  
Office Address P. O. Box 349 Russell, Kansas 67665  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 2-1-71 19  
Plugging completed 2-5-71 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well 3953 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	961	None
				5 1/2	3953	3181'.69

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


Pushed plug to 3850'. Sanded to 3830' and dumped 5 sacks of cement. Shot casing at 3211'. Laid down 97 joints of 5 1/2" casing. Pushed a plug to 375' and dumped 25' rock bridge. Plugged well with 3 1/2 yards of ready mix concrete.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 26 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Forbes Casing Pulling Company, Inc.  
Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn, deposes and says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) James W. Rockhold  
P. O. Box 221 Great Bend, Kansas (Address)

Subscribed and sworn to before me this 15 day of February 1971

(Signature) Notary Public

DRILLING RECORD

15-145-19021-0000

Well No, 2 T. A. Malin  
NW NW NW Sec. 1-22S-16W  
Pawnee County, Kansas

Casing Record

970' of 8-5/8" OD Surface Pipe  
cemented with 500 sacks.

3953' of 5 1/2" OD Casing cemented  
with 100 sacks.

Work Commenced 2/8/52  
Drilling Commenced 2/8/52  
Drilling Completed 2/24/52  
Work Completed 2/26/52

WELL LOG

Sand	0 to	40
Sand & Clay	40 to	145
Shale	145 to	304
Shale & Shells	304 to	392
Sand	392 to	495
Shale & Sand	495 to	625
Red Bed	625 to	800
Shale	800 to	915
Red Bed & Shale	915 to	950
Anhydrite	950 to	973
Shale & Shells	973 to	1520
Shale	1520 to	1600
Shale & Shells	1600 to	1780
Bro. Lime	1780 to	1885
Lime & Shale	1885 to	2090
Bro. Lime	2090 to	2200
Lime & Shale	2200 to	2870
Lime	2870 to	2975
Lime & Shale	2975 to	3240
Lime	3240 to	3445
Shale & Lime	3445 to	3493
Lime	3493 to	3820
Conglomerate	3820 to	3860
Simpson	3860 to	3862
Sand & Shale	3862 to	3885
Simpson	3885 to	3923
Arbuckle Lime	3923 to	3953 TD

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 23 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Top Arbuckle 3919 - DST 3920-3923 rec.  
30' oil cut mud & 30' sulphur water.

Lane-Wells plug set at 3903  
Perforated Simpson Sand 3861-3862 w/ 15 shots  
Well flowed 39 bbls. in 2 hours, no water.

C E R T I F I C A T I O N

State of Oklahoma, County of Tulsa SS

I, Herrick Babcock, Partner of Iron Drilling Company, Certify that  
the above is a true and correct log of the above described well.

*Herrick Babcock*

Subscribed to and sworn before me this 5th day of March, 1952.

*B. Michal*  
Notary Public

My commission expires Feb. 28, 1956