

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-26692-00-00  
Spot: SWNWNW Sec/Twnshp/Rge: 3-34S-8E  
4325 feet from S Section Line, 4948 feet from E Section Line  
Lease Name: FULSOM B Well #: 1  
County: CHAUTAUQUA Total Vertical Depth: 2500 feet

Operator License No.: 6101  
Op Name: TEICHGRAEBER OIL, INC.  
Address: 700 N MAIN ST  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2491		125 SX
SURF	8.625	501		235 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/22/2016 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: RICK STOUT Company: \_\_\_\_\_ Phone: (620) 583-2173

Proposed Plugging Method: Circulate to TD. Spot cement thru tubing at perforations, 2476'-2479' with 50' plug. Recover approx. 1500' of 5.5" casing, spot 50' middle plug right above the Kansas City formation thru tubing, then come up to 500'm then cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/23/2016 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 2450' gelled hole and spotted 10 sack plug. Pulled up to 1600' and spotted 10 sack plug. Pulled 1" and perforated casing at 550'. Ran 1" back into 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 180 sacks of cement were used to plug this well.

Perfs: \_\_\_\_\_  
**KCC WICHITA**  
**FEB 06 2017**  
**RECEIVED**  
  
**RECEIVED**  
**KCC DIST # 3**  
**FEB 01 2017**  
**CHANUTE, KS**  
*DS*

Remarks: WELL WAS PLUGGED DUE TO INACTIVE WELL LIST.

Plugged through: TBG

District: 03

Signed *Duane A Sims*  
(TECHNICIAN)

INVOICED  
FEB - 8 2017