

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-131-20151-00-00  
Spot: SWNENW Sec/Twnshp/Rge: 17-4S-14E  
4290 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: SWART A Well #: 1  
County: NEMAHA Total Vertical Depth: 3753 feet

Operator License No.: 31142  
Op Name: PETROLEUM PROPERTY SERVICES, IN  
Address: 125 N MARKET SUITE 1251  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3752		150 SX
SURF	8.625	362		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/20/2016 12:00 PM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: CHUCK TONER Company: PETROLEUM PROPERTY SERVICE Phone: (620) 546-4752

Proposed Plugging Method: PER KCC INSTRUCTIONS

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE  
Date/Time Plugging Completed: 12/21/2016 10:00 PM KCC Agent: TAYLOR HERMAN

**Actual Plugging Report:**

PERFORATED THE CASING AT 1190' AND 300'. RAN TUBING DOWN TO 3706' INSIDE THE PRODUCTION CASING AND PUMPED 25 SACKS OF CEMENT. PULLED THE TUBING UP TO 1190' AND PUMPED 37 SACKS OF CEMENT INSIDE AND OUTSIDE THE PRODUCTION CASING. PULLED THE TUBING UP TO 300' AND CIRCULATED 75 SACKS OF CEMENT TO THE SURFACE ON THE INSIDE AND OUTSIDE OF THE PRODUCTION CASING.

**Perfs:**

Top	Bot	Thru	Comments
3692	3702		
3666	3672		

RECEIVED  
KCC DIST # 3  
FEB 02 2017  
CHANUTE, KS  
TH  
KCC WICHITA  
FEB 06 2017  
RECEIVED

Remarks:  
Plugged through: TBG

District: 03 Signed Taylor C. Herman  
(TECHNICIAN)