

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-23482-00-00
Spot: S2NESWNW Sec/Twnshp/Rge: 11-30S-6E
3505 feet from S Section Line, 990 feet from W Section Line
Lease Name: BETTY Well #: 2
County: COWLEY Total Vertical Depth: 2415 feet

Operator License No.: 5437
Op Name: TOMCO OIL, INC.
Address: 22150 SE COLE CREEK RD
ATLANTA, KS 67008

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2410		165 SX
SURF	8.625	315		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/15/2016 12:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: TOM BLAIR Company: _____ Phone: (620) 394-2324

Proposed Plugging Method: SET CEMENT PLUG @ 1000 FT. PERFORATE 5.5 IN. CASING @ 400 FT. CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: JONATHAN HILL Witness Type: PARTIAL
Date/Time Plugging Completed: 12/15/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

CIBP SET @ 2240 W/2 SX. PERFORATE 365', ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 90 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCULATED. TICKET #3029. 12-15-2016 RIH W/1" TUBING AT 260', ELITE ESTABLISHED CIRCULATION, MIXED & PUMPED 45 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. TICKET #3088.

Perfs:

Top	Bot	Thru	Comments
2356	2362	CSG	

Remarks:

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

INVOICED ^{Form CP-2/3}

FEB - 8 2017