

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-20735-00-00
Spot: NWNESWSE Sec/Twnshp/Rge: 9-35S-4E
1246 feet from S Section Line, 1742 feet from E Section Line
Lease Name: FRANK BOSSI Well #: 2
County: COWLEY Total Vertical Depth: 3370 feet

Operator License No.: 33405
Op Name: ANSTINE & MUSGROVE INC.
Address: PO BOX 391
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3369		150 SX
SURF	8.625	164		135 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/06/2016 8:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: GARY ANSTINE Company: ANSTINE & MUSGROVE Phone: (620) 441-8165

Proposed Plugging Method: AS PER KCC RULES & REGS / CIBP @ 3250 W/4 SXS, PERF & CIRC 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 12/07/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3250', DUMP BAILED 4 SXS CEMENT ON TOP. RIH ON WIRELINE PERFORATED SQUEEZE HOLES @ 250'-251'. RIH W/TBG @ 256', CONSOLIDATED OILWELL SERVICES MIXED & PUMPED 160 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. 12-7-2016, TAGGED CEMENT @ 160'. CMC DUMPED 20 SXS 60/40 POZMIX 4% GEL TO SURFACE. PLUG DOWN 12-7-2016 5:00 PM. CONSOLIDATED CEMENT TICKET #51939. CMC CEMENT TICKET # 341711.

Perfs:

Top	Bot	Thru	Comments
3313	3323	CSG	
3292	3302	CSG	

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

INVOICED
FEB - 8 2017

Form CP-2/3

✓