

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-057-20880-00-00  
Spot: SWSESWNE Sec/Twnshp/Rge: 23-27S-24W  
2700 feet from S Section Line, 1970 feet from E Section Line  
Lease Name: TAMI Well #: 1-23  
County: FORD Total Vertical Depth: 5198 feet

Operator License No.: 34318

Op Name: BEREXCO LLC

Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4800		WITH 2 SX CMT
DVT		1600		WITH 350 SX CMT
PROD	5.5	5190	0	WITH 720 SX CMT
SURF	8.625	605		WITH 325 SX CMT

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/10/2017 1:00 PM

Plug Co. License No.: 34082

Plug Co. Name: ALLIANCE WELL SERVICE INC.

Proposal Rcvd. from: BARRY WALTERS

Company: ALLIANCE WELL SERVICE INC.

Phone: (620) 672-9100

Proposed  
Plugging  
Method:

CIBP @ 4803' WITH 2 SX CMT. TBG TO 1640' & CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: ERIC MACLAREN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 01/10/2017 2:45 PM

KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

SET CIBP @ 4800' WITH 2 SX CMT. RAN TBG TO 1652' & PUMPED 200 SX CMT TO FILL 5 1/2" CASING. PRESSURED THE BACKSIDE TO 500# WITH 4 SX CMT.

Top	Bot	Thru	Comments
4853	4857		


Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed 

(TECHNICIAN)

RECEIVED  
FEB - 6 2017  
KCC DODGE CITY 

INVOICED  
FEB - 8 2017

Form CP-2/3