

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-20377-00-00
Spot: SESENESE Sec/Twnshp/Rge: 29-34S-29W
1345 feet from S Section Line, 329 feet from E Section Line
Lease Name: ADAMS Well #: 1-29
County: MEADE Total Vertical Depth: 6302 feet

Operator License No.: <u>35300</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>COACHMAN ENERGY OPERATING CO</u>	CIBP		5830		WITH 2 SX CMT
Address: <u>1125 17TH ST., SUITE 410</u>	PROD	4.5	6302	0	WITH 150 SX CMT
<u>DENVER, CO 80202</u>	SURF	8.625	1481		WITH 750 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/26/2017 2:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED OPS, LLC
Proposal Revd. from: GERALD WALKER Company: PROFESSIONAL PULLING SERVIC Phone: (785) 731-5018

Proposed Plugging Method: SET CIBP @ 5830' WITH 2 SX CMT. PERFORATE AT 1530' & PUMP 10 SX GEL & 50 SX CMT WITH 100# HULLS IN LAST 25 SX CMT. PERFORATE AT 550' & PUMP CMT TO SURFACE.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 01/26/2017 7:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 5830' WITH 2 SX CMT. 1ST PLUG PERFORATE AT 1515' & PUMP 10 SX GEL & 50 SX CMT. 2ND PLUG PERFORATE AT 513' & PUMPED 150 SX CMT. HAD CMT IN 4 1/2" BUT NOT ANNULUS, RAN OUT OF CMT. BROUGHT MORE CMT & PUMPED CMT TO SURFACE WITH ADDITIONAL 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5930	5971		
5883	5887		

Remarks: USED 60/40 POZMIX 4% GEL & CLASS A CEMENT BY ALLIED.

Plugged through: TBG

District: 01

Signed

Larry Harris ECRS
(TECHNICIAN)

RECEIVED
JAN 30 2017
KCC DODGE CITY

MD

SR

INVOICED
FEB - 8 2017

Form CP-2/3