

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-23772-00-00  
Spot: NESWSE Sec/Twnshp/Rge: 32-29S-4E  
3167 feet from S Section Line, 3329 feet from E Section Line  
Lease Name: ROCK Well #: 1-32  
County: BUTLER Total Vertical Depth: 3050 feet

Operator License No.: 35269

Op Name: CK OIL & GAS LLC

Address: 906 E. TRAPP ST.  
HERINGTON, KS 67449

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3021	1450	235 SX CMT
SURF	8.625	240		165 SX CMT

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/09/2016 8:00 AM

Plug Co. License No.: 30483

Plug Co. Name: KREMEIER, LES (DECEASED)ESTATE DBA KREMEIER PROD & OPER

Proposal Rcvd. from: CHRIS KREMEIER

Company:

Phone: (785) 307-5701

Proposed Plugging Method: AS PER KCC RULES AND REGS

Plugging Proposal Received By: DUANE KRUEGER

Witness Type: PARTIAL

Date/Time Plugging Completed: 11/14/2016 5:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

CIBP SET @ 2930 W/2 SX CEMENT ON TOP. CUT CASING @ 1450', LAYED DOWN CASING. RIH W/TUBING @ 317'. ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 115 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED.

Top	Bot	Thru	Comments
2983	2986		

Remarks: COMPLIANCE/ 10 YR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER  
(TECHNICIAN)

INVOICED  
FEB - 8 2017

Form CP-2/3

JK