

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513.

API Well Number: 15-015-23770-00-00
Spot: NWSENWSW Sec/Twnshp/Rge: 29-29S-4E
1878 feet from S Section Line, 4323 feet from E Section Line
Lease Name: ROCK Well #: 1-29
County: BUTLER Total Vertical Depth: 3073 feet

Operator License No.: 35269
Op Name: CK OIL & GAS LLC
Address: 906 E. TRAPP ST.
HERINGTON, KS 67449

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3073	1450	250 SX CMT
SURF	8.625	257		165 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/09/2016 8:00 AM
Plug Co. License No.: 30483 Plug Co. Name: KREMEIER, LES (DECEASED)ESTATE DBA KREMEIER PROD & OPER
Proposal Revd. from: CHRIS KREMEIER Company: _____ Phone: (785) 307-5701

Proposed Plugging Method: AS PER KCC RULES AND REGS.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/14/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

CIBP @ 2960 W/ 2 SKS, CUT CASING @ 1450'. LAYED DOWN 5 1/2" CASING. RIH W/TBG @ 315'. ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 90 SXS 60/44 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #3013.

Remarks: COMPLIANCE / 10 YEAR

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

INVOICED

FEB - 8 2017

Form CP-2/3

✓