

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-26205-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 9-32S-11E  
4367 feet from S Section Line, 4146 feet from E Section Line  
Lease Name: HUDSON Well #: 2  
County: CHAUTAUQUA Total Vertical Depth: 1945 feet

Operator License No.: 8736  
Op Name: DIXON, JAMES DAVID  
Address: 1214 CYCLONE  
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1941		100 SX
SURF	8.625	331		185 SX
SURF		1941		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/25/2017 10:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: JAMES D. DIXON Company: \_\_\_\_\_ Phone: (620) 647-3317

Proposed Plugging Method: 1" to bottom, with gel in hole, spot 10 sacks, pull up to 1,000 ft., 5 sacks cement, pull up to 500 ft. and cement to surface

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/25/2017 10:00 AM KCC Agent: DUANE SIMS

**Actual Plugging Report:**

Ran 1" to 1530' gelled hole and spotted 5 sack plug. Pulled 1" and perforated casing at 880' and 550'. Ran 1" back into 880' and spotted 10 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 184 sacks of cement were used to plug this well. Well was cut off and locaiton restored.

**Perfs:**


Top	Bot	Thru	Comments
1870	1893		
RECEIVED KCC DIST # 3 FEB 01 2017 CHANUTE, KS DS KCC WICHITA FEB 06 2017			

Remarks: WELL WAS PLUGGED DUE TO INACTIVE WELL LIST.

RECEIVED

Plugged through: TBG

District: 03

Signed   
(TECHNICIAN)

INVOICED Form CP-2/3  
FEB - 8 2017