

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-26288-00-00  
Spot: NWSENESE Sec/Twnshp/Rge: 23-28S-14E  
1780 feet from S Section Line, 500 feet from E Section Line  
Lease Name: J BAKER Well #: 1  
County: WILSON Total Vertical Depth: 1230 feet

Operator License No.: 33718  
Op Name: MEARS, JOHN C.  
Address: 4100 240TH RD  
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1208		
SURF	8.625	43		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/21/2016 8:00 AM  
Plug Co. License No.: 33977 Plug Co. Name: E K ENERGY LLC  
Proposal Rcvd. from: DAVE KIMZEY Company: JOHN C. MEARS Phone: (620) 496-6257

Proposed Plugging Method: Run cement string to TD and spot 50' plug, raise pipe to 500' and spot 50' cement plug, raise pipe to 250' and then fill to surface.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE  
Date/Time Plugging Completed: 12/21/2016 8:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A one inch cement string was lowered to 1200 ft and a 50 ft cement plug spotted. The cement string was raised to 500 ft and a 50 ft cement plug was spotted. The cement string was raised to 250 ft and then filled to surface with cement. A total of 35 sacks of portland cement were used to plug well (gel spacers between cement plugs). The well was cut off below plow depth and the location restored.

Perfs:

RECEIVED  
KCC DIST # 3  
JAN 31 2017  
CHANUTE, KS

AD

KCC WICHITA  
FEB 06 2017  
RECEIVED

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning  
(TECHNICIAN)

Form CP-2/3

INVOICED  
FEB - 8 2017