

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-32297-00-00
Spot: NENESW Sec/Twnshp/Rge: 13-34S-13E
2260 feet from S Section Line, 2783 feet from E Section Line
Lease Name: HOLLANDSWORTH Well #: 6
County: MONTGOMERY Total Vertical Depth: 1300 feet

Operator License No.: 9749
Op Name: MELANDER, CHRIS DBA CHRIS MELA
Address: 2256 CR 2500
CANEY, KS 67333

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.375	836		154 SX
PROD	3	875		154 SX
SURF	7	20		21 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/13/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: CHRIS MELANDER Company: _____ Phone: (620) 289-4723

Proposed Plugging Method: Remove 1" tubing. Remove insert pump. Run 1" tubing to bottom. Fill casing from Total Depth to Surface with Portland Type 1. Cut casing off below ground level. Restore location.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed: 09/13/2016 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:
Ran 1" to 875' gelled hole and spotted 2 sack plug. Pulled up to 500' and spotted 2 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 12 sacks of cement were used to plug this well. Well has not been cut off as of January 18, 2017.

Perfs: **KCC WICHITA**
FEB 06 2017
RECEIVED

RECEIVED
KCC DIST # 3
FEB 01 2017
CHANUTE, KS
DS

Remarks: WELL WAS PLUGGED DUE TO OPERATOR RELEASING THE LEASE BACK TO LANDOWNER.

Plugged through: TBG

District: 03

Signed *DS*
(TECHNICIAN)

Form CP-2/3
INVOICED
FEB - 8 2017