

9-24-87 15-083-10025-0000

1 050935

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion 6/9/63
C NE NE, SEC. 35, T 22 S, R 23 W/E
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5229

Lease Name Billings "B" Well # 1
County Hodgeman 146.25
Well Total Depth 4500 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 250

Operator: Phillips Petroleum Company
Name & Address Route #3, Box 20-A
Great Bend, KS 67530

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B.J. Titan License Number _____

Address 2601 NW Expressway, Suite 710W, Oklahoma City, OK 73112

Company to plug at: Hour: 10:45 a.m. Day: 24 Month: 9 Year: 19 87

Plugging proposal received from G.L. Kelso

(company name) Phillips Petroleum Company (phone) 316-793-8424

were: 5 1/2" at 4493' Open hole 4493-4500'

1st plug set 5 1/2" CIBP at 4450' and dump 2 sx cement on top with a bailer,

2nd plug perforate 5 1/2" casing at 850' and pump 125 sx cement down 5 1/2"

3rd plug pump 100 sx cement down 8 5/8" X 5 1/2" annulus.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p. Day: 24 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug set 5 1/2" CIBP at 4450' and dumped 2 sx cement on top
with bailer,

2nd plug perforated 5 1/2" casing at 850' and pumped 125 sx of cement down 5 1/2"
Maximum pressure 100 and shut in 0 psi.

3rd plug pumped 100 sx of cement down 8 5/8" X 5 1/2" annulus.
Maximum pressure 600 psi and shut in 200 psi.

Remarks: Used Thrifty Mix by B.J. Titan. No recovery.
(If additional description is necessary, use BACK of this form.)

(If desired, plugging contractor observe this plugging.)

INVOICED

DATE 10-6-87

INV. NO. 18396

Signed Richard W. Lucas
(TECHNICIAN)

09-24 OCT 29 1987