

AFFIDAVIT OF COMPLETION FORM

ACO-1

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.


OPERATOR Pendleton Land and Exploration, Inc. API NO. 15-083-20,912-0000  
 ADDRESS 23 Inverness Way East COUNTY Hodgeman  
Englewood, CO 80112 FIELD wildcat

\*\*CONTACT PERSON Lee Brian VanRamshorst RECEIVED PROD. FORMATION -----  
 PHONE 303/773-1776 STATE CORPORATION COMMISSION LEASE Ruff

PURCHASER ----- WELL NO. C #1  
 ADDRESS ----- 12-7-8/CONSERVATION DIVISION WELL LOCATION 100' S of SW SW SE  
----- Wichita, Kansas

DRILLING Buffalo Drilling Co., Inc. 230 Ft. from S Line and  
 CONTRACTOR 2310 Ft. from E Line of  
 ADDRESS 435 Page Court - 220 W. Douglas the SE 1/4 SEC. 24 TWP. 22S RGE. 22W  
Wichita, KS 67202

PLUGGING Buffalo Drilling Co. Inc.  
 CONTRACTOR  
 ADDRESS 435 Page Court - 220 W. Douglas  
Wichita, KS 67202



WELL PLAT  
 KCC   
 KGS   
 MISC   
 (Office Use)

TOTAL DEPTH 4550' PBDT -----  
 SPUD DATE 9/30/81 DATE COMPLETED 10/16/81  
 ELEV: GR 2251' DF ----- KB 2256'

DRILLED WITH ~~(CANYON)~~ (ROTARY) ~~(ANY)~~ TOOLS (New) / ~~(Used)~~ casing.  
 CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	1518'	Class H Common	400 200	3% CaCl, 4% gel 3% CaCl, 2% gel


LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Plugged: @ 1500' w/ 60 sx	
@ 330' w/ 50 sx	
@ 40' w/ 10 sx, 5 sx in rat hole	

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF
Disposition of gas (vented, used on lease or sold)	Water %	Gas-oil ratio bbls.
	Perforations	

\*\*The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.



Name of lowest fresh water producing stratum Dakota Depth 200'

Estimated height of cement behind Surface Pipe circ to surface.

DV USED? no

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
DST #1/4470-4507/Miss/30"42"30"66". Rec 10' oil specked mud, CI 46,000. IHP 2411, IFP 50-51, ICIP 1356, FHP 2378, FFP 67-67, FCIP 1367, BHT 124°F.			Log tops: Heebner Lansing/KC Marmaton Ft Scott Cherokee Miss	3830 (-1574) 3893 (-1637) 4272 (-2016) 4427 (-2171) 4452 (-2196) 4504 (-2248)
DST #2/4470-4512/Miss/30"45"60"57" Rec 80' DM, CI 60,000. IHP 2468, IFP 85-91*, ICIP 1236, FHP 2336, FFP 102-112, FCIP 1266, BHT 118°F. *Pressures questionable due to plugging action.			BKC Pawnee	4202 (-2146) 4385 (-2129)
DST #3/4459-4520/Miss/25"48"55"66". Rec 100' DM, CI 60,000. IHP 2379, IFP 86-86, ICIP 1284, FHP 2373, FFP 102-102, FCIP 1265, BHT 119°F.			Logs run: Gamma Ray Neutron RA/G BHCS	300'-1517'
DST #4/4042-4145/KC/35"48"90"90". Rec 1080' muddy water, CI 76,000. IHP 2116, IFP 119-207, ICIP 1378, FHP 2095, FFP 233-377, FCIP 1368, BHT 116°F.				

AFFIDAVIT

STATE OF Colorado, COUNTY OF Arapahoe SS,

Lee Brian VanRamshorst OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,  
DEPOSES THAT HE IS Manager of Operations (FOR)(OF) Pendleton Land and Exploration, Inc.  
OPERATOR OF THE Ruff LEASE, AND IS DULY AUTHORIZED TO MAKE  
THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. C-1 ON  
SAID LEASE HAS BEEN COMPLETED AS OF THE 16th DAY OF October, 1981, AND THAT  
ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.  
FURTHER AFFIANT SAITH NOT.

(S) Lee Brian VanRamshorst

SUBSCRIBED AND SWORN BEFORE ME THIS 1st DAY OF December 1981

MY COMMISSION EXPIRES: September 21, 1985

Emily Ann Downs  
NOTARY PUBLIC  
Emily Ann Downs  
23 Inverness Way East  
Englewood, CO 80112