



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 23 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Roy Cook of Imperial Oil Of Kansas has this  
 date requested permission to plug the following described well:

Mr. Roy Cook guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Of Kansas

Complete Address: 780 4th. Natl. Bldg. Wichita, Kansas

Lease Name: Billings Well No. # 3

Location: C SW SW Sec. 25 Twp. 22 Rge. 23 (E) (W)

County Hodgeman Total Depth 4582 Oil Well x

Gas Well    Input Well    SWD Well    D & A x Lost Hole   

Mr. Roy Cook was instructed to plug the well as follows:

8 5/8" 1447' Circulated w/cement.

Mud 4582' to 500' Plug, Hulls, 1, 20 Sax. cement 500' to 440'

Mud 440' to 300' Plug, Hulls, 15 Sax. cement 300' to 255'

Mud 255' to 40' Plug, Hulls, 10 sax. cement 40' to surface.

Very truly yours,

*[Signature]*  
 Conservation Division Agent