



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 13 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Walker of Adair Oil Co. has this

date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Adair Oil Co.

Complete Address: 1005 2nd, Wichita, Kansas

Lease Name: Campbell Well No. 1

Location: SW NW Sec. 9 Twp. 22 Rge. 23 (EX(W))

County: Hodgeman Total Depth 4649' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

8 5/8" to 286' circulated w/cement. Mud 4649' to 900'

Spot 80 sacks cement 900' to 600'. Mud 600' to 280'

Spot 30 sacks cement 280' to 180'. Mud 180' to 40'.

Plug, Halls & 15 sacks cement 40' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent