



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUL 8 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Krier of Imperial Oil Of Kansas has this date requested permission to plug the following described well:

Mr. Krier guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Of Kansas

Complete Address: Box 97 Wakeeney, Kansas

Lease Name: Hertel Well No. # 2

Location: C SE SW Sec. 26 Twp. 22 Rge. 22 (E) (W)

County Hodgeman Total Depth 4510' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Krier was instructed to plug the well as follows:

8 5/8"-239' Circulated w/cement. 5 1/2"-4509' Cemented. Plug back to 4432'

Perforations 4420' - 4426'

Plug bottom w/sand 4432' to 4400' 5 Sax.cement 4400' to 4360'

Heavy mud 4360' to 600' 200 Sax.cement 600' to surface.

Very truly yours,

[Signature]
 Conservation Division Agent