



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 7 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

10-7-1963

Dear Sir:

Mr. Waston of Schultz, Turner & Webb has this

date requested permission to plug the following described well:

Mr. Waston guarantees payment of the plugging fee.

Operator's full Name: Schultz, Turner & Webb

Complete Address: 1940 Mercantile Dallas Bldg. Dallas, Texas

Lease Name: Ewy Well No. A-2

Location: C SW SE Sec. 17 Twp. 22 Rge. 22 (E) (W)

County Hodgeman Total Depth 4536' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Waston was instructed to plug the well as follows:

8 5/8"-296' Circulated w/200 Sax.cement. 4 1/2"-4534' Cemented w/150 Sax.

Perforations-4474' to 4484' Hole plug w/packer and tubing top at 4320'.

Dump 5 Sax.cement 4320' to 4260' Mud 4260' to 700'

25 Sax.cement spotted 700' Mud top cement to 275'

25 Sax.cement spotted 275' to 200' Mud 200' to 50'

10' rock bridge 50' to 40' 15 Sax.cement 40' to surface.
Very truly yours,

[Signature]
Conservation Division Agent