

State of Kansas



15.083.10056.00.00

FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 1 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Tom Buffington of Red Tiger Drilling Co. has this date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Frontier Oil Co.

Complete Address: 1720 Wichita Plaza, Wichita, Kansas

Lease Name: Sinclair Well No. # 1

Location: C NW SW Sec. 2 Twp. 21 Rge. 26 (E) (W) W

County Hodgeman Total Depth 4552 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Buffington was instructed to plug the well as follows:

360' of 8 5/8" surface pipe, cement circulated with 185  
sacks. Fill hole with mud to 300', 1st cementing plug,  
1/4 sack hulls, cement with 20 sacks. Fill hole with mud to  
40', 2nd cementing plug, 1/4 sack hulls, cement with 10  
sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent