



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1964

CONSERVATION DIVISION
Wichita, Kansas

3-23-1964

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Morgan of Hudson Petroleum Co. has this
 date requested permission to plug the following described well:

Mr. Morgan guarantees payment of the plugging fee.

Operator's full Name: Hudson Petroleum Co.

Complete Address: Box 333 Kansas City, Kansas

Lease Name: Stoskoff Well No. # 1

Location: C SW SW Sec. 24 Twp. 21 Rge. (E) (W) 25

County Hodgeman Total Depth 4515' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Morgan was instructed to plug the well as follows:

8 5/8"-574' Circulated w/cement.

Mud 4515' to 700' Spotted 25 Sax. cement 700' to 625'

Mud 625' to 500' Spotted 25 Sax. cement 500' to 425'

Mud 425' to 45' Plug, Halls, 15 Sax. cement 45' to 0

Very truly yours,

F. Hugh Scott
 Conservation Division Agent