



15.083.20296.00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 28 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Glenn of Pet Inc. has this

date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: R.R. 2, Great Bend, Kansas

Lease Name: Vieux "D" Well No. 2

Location: App C SW SE Sec. 11 Twp. 21 Rge. 25 ~~(E)~~ (W)

County: Hodgeman Total Depth 4511' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Glenn was instructed to plug the well as follows:

8 5/8" to 404' circulated w/ cement. 5 1/2" to 4502' cemented.


Top perforations 4480' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4410' Mud 4410' to 450'

Spot 50 sacks cement 450' to 300' Mud 300' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent