



15.083.20372.00.00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Pulley of Oasis has this

date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: ~~OKERS~~ Oasis Petroleum Inc.

Complete Address: 3535 NW 58th St. Oklahoma City, Oklahoma

Lease Name: Everton Well No. 4

Location: C NW SE Sec. 34 Twp. 21 Rge. 24 (E) (W)

County: Hodgeman Total Depth 4715' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:


8 5/8" to 675' circulated w/ cement. 5 1/2" to 4710' cemented.

Top perforations 4646' Plug bottom w/ Bridge Plug At 4622'

Mud 4622' to 500' Spot 50 sacks cement 500' to 350'

Mud 350' to 150' Plug, Halls & 50 sacks cement 150' to 0'

Very truly yours,


Conservation Division Agent