



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 12 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Morton of Texaco has this

date requested permission to plug the following described well:

Mr. Morton guarantees payment of the plugging fee.

Operator's full Name: Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name: A.L. Bengtson Well No. 1

Location: C NE SW Sec. 12 Twp. 21 Rge. 41 ^{XX} (E) (W)

County: Hamilton Total Depth 2812' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Morton was instructed to plug the well as follows:

7" to 250' circulated w/ cement. 4 1/2" to 2812' circulated w/ cement.

Top perforations 2782' Plug bottom w/ 15 sacks cement

Top of cement 2640' Mud 2640' to 1200'

Spot 110 sacks cement 1200' to 0'.

Very truly yours,

Edgar J. Evers
Conservation Division Agent