



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

MAY 4 - 1972  
05-02-72  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Valintine of L V O has this date requested permission to plug the following described well:

Mr. Valintine guarantees payment of the plugging fee.

Operator's full Name: L V O Corporation

Complete Address: Box 2848, Tulsa, Oklahoma

Lease Name: A. M. Howell Well No. 1

Location: NW SE Sec. 21 Twp. 21 Rge. 41 (E)(W)

County: Hamilton Total Depth 2813' Oil Well

Gas Well X Input Well      SWD Well      D & A      Lost Hole     

Mr. Valintine was instructed to plug the well as follows:

9 5/8" to 320' circulated w/ cement. 4 1/2" to 2813' cemented.

Top perforations 2640' Plug bottom w/ 20 sacks cement.

Top of cement 1426' Mud 1426' to 320'

Spot 35 sacks cement 320' to 220'. Mud 220' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent