



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Valentine of LVO has this

date requested permission to plug the following described well:

Mr. Valentine guarantees payment of the plugging fee.

Operator's full Name: LVO Corporation

Complete Address: Box 2848, Tulsa, Oklahoma

Lease Name: UNIT 1711 Well No. 1

Location: C NW SE Sec. 17 Twp. 21 Rge. 41 (E) (W)

County: Hamilton Total Depth 2800' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Valentine was instructed to plug the well as follows:

8 5/8" to 121' circulated w/ cement. 4 1/2" to 2793' cemented.

Top perforations 2750' Plug bottom w/ 20 sacks cement.


Top of cement 2616' Mud 2616' to 600'

Spot 35 sacks cement 600' to 500' Mud 500' to 150'

Spot 40 sacks cement 150' to 50' Mud 50' to 45'

Plug, HULLS & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent