

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-009-15069-0000
API NUMBER July 23, 1940
LEASE NAME Esfeld

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER # 2
2130 3150 KCC 1-20-17
330 Ft. from S Section Line
330 Ft. from E Section Line
SEC. 30 TWP. 16 S RGE. 11 W or (W)
COUNTY Barton
Date Well Completed July 1940
Plugging Commenced 8/17/94 (9 a.m.)
Plugging Completed 8/17/94 (10:15)

LEASE OPERATOR American Warrior Inc.

ADDRESS Box 399; Garden City, Ks. 67846

PHONE# (316) 275-9231 OPERATORS LICENSE NO. 4058

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/12/94 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Kansas City Depth to Top 2921' Bottom 2978' T.D. 3117'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	395	8 5/8	395	none
	casing	0	3117	5 1/2	3117	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforated 1470', 740' and 410'. Mix 25 sks. cement, 10% gel. Mix cement with 350# hulls. Mix 100 sks. cement, Mix cement with 150# hulls. Mix 90 sks. cement. Shut in 200#. Maximum pressure 700#. Tie on Braden head. Mix 30 sks. cement, 10% gel. Maximum pressure 300#. Close in 50#. 8/19/94 Cement down 20'. Halliburton
(If additional description is necessary, use BACK of this form.) ticket #621863

Name of Plugging Contractor Halliburton License No. _____

Address Hays, Ks. 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Warrior Inc.


STATE OF KANSAS COUNTY OF ELLIS, ss. _____

Dean Dues (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

(Signature) Dean Dues

(Address) 1209 Honey Hays, Ks.

SUBSCRIBED AND SWORN TO before me this 25th day of August, 1994.



Charlotte Weber
Notary Public

My Commission Expires: _____

RECEIVED
STATE CORPORATION COMMISSION

AUG 26 1994