


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Flat

Barton County. Sec. 30 Twp. 16 Rge. 11 (E) W (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE SW  
Lease Owner B & R Drilling, Inc.  
Lease Name Oeser Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 14, 1947 19  
Application for plugging filed April 19, 1951 19  
Application for plugging approved April 19, 1951 19  
Plugging commenced April 19, 1951 19  
Plugging completed April 23, 1951 19  
Reason for abandonment of well or producing formation All Oil Recovered

If a producing well is abandoned, date of last production April 6, 1951 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough  
Producing formation Depth to top Bottom Total Depth of Well 3049' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10 3/4" 7"	347' 3048'	None 2107'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging Record

Plugged back with crushed rock from 3280' to 3000',  
dumped 6 sax of cement at 3000' with dump bailer.  
Top of cement 2965'. Filled with mud to 300', set  
rock bridge, dumped 20 sax of cement, top of cement  
240', filled with mud to 20', dumped 10 sax of  
cement for cap.

5-3-51

FILE  
STATE CORPORATION COMMISSION  
MAY 3 - 1951  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Correspondence regarding this well should be addressed to B & R DRILLING, INC.  
Address RUSSELL, KANSAS

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
W. A. Michaelis, Jr. (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. A. Michaelis, Jr.  
Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of May, 1951

Notary Public

My commission expires 6-17-54

PLUGGING  
FILE SEC 30 T 16 R 11 W  
BOOK PAGE 78 LINE 2

B & R DRILLING, INC.  
 OESER COMMUNITY #1

SEC. 30 TWP. 16 NGL. 11  
 COUNTY: BARTON, KANSAS

TOTAL DEPTH: 3049'  
 COME: 10/3/47 - COMP: 10/14/47

TOP TUPEKA - 2692'  
 " HEEGNER - 2934  
 " DROWN LINE - 3028  
 " LANSING K.C. - 3042

CASING  
 10 JTB. 10 1/2" SET AT 347'  
 94 JTB. 7" SET AT 3048'

CEMENT  
 150 SX - CIRCULATED  
 90 SX

FORMATION:	DEPTH:
SHALE & SHELLS	80'
SAND	95
SHALE & SHELLS	240
SHALE, SAND & PYRITE	330
SHALE	360
SAND	495
SANDY SHALE	520
RED BED	745
ANHYDRITE	775
SHALE & SHELLS	1025
SALT & SHALE	1225
SHALE & SHELLS	1410
LIME & SHALE	2160
SHALE, LIME & SHELLS	2250
SHALE & LIME	2314
BROKEN LIME	2344
SHALE & LIME	2755
LIME	2960
SHALE	3020
LIME	
SHALE	
LIME	

STATE OF KANSAS )  
 ) SS  
 IN SELL COUNTY )

FILED  
 STATE OF KANSAS  
 3049  
 MAY 3 - 1951  
 CONSERVATION DIVISION  
 Wichita, Kansas

I HEREBY CERTIFY THAT THE ABOVE INFORMATION IS TRUE  
 AND CORRECT TO THE BEST OF MY KNOWLEDGE.

*Sam C. Fritch*

SUBSCRIBED AND SWORN TO BEFORE ME THIS 18TH DAY OF OCTOBER, 1947.

*Cora Lumme*

MY COM. EXPIRES 6/17/50

NOTARY PUBLIC

PLUGGING  
 FILE SEC. 30 TWP. 16 NGL. 11  
 PAGE 28 LINE 3