


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15009-03134-0000

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton

County. Sec. 30 Twp. 16S Rge. 11W (E) (W)

Location as "NE/CNW/SW" or footage from lines. CWL SE SE

Lease Owner Brunson Drilling Co., Inc.

Lease Name Krier "A" Well No. 8

Office Address 333 First Nat'l. Bldg. - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil well

Date well completed August 25 19 54

Application for plugging filed July 24 19 56

Application for plugging approved July 25 19 56

Plugging commenced July 26 19 56

Plugging completed July 28 19 56

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19 ____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Brundage

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3264 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	381'	None
				5-1/2"	3263'	2596'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled the hole with sand from 3264' to 3110' and ran 5 sacks of cement. Bailed the hole down and set a 10' rock bridge at 310'. Ran 20 sacks of cement at 300'. Mixed and ran 20 sacks of jell mud and 10 sacks of cement to fill to base of cellar. Plugging completed.

8-1-56

STATE OF KANSAS
CORPORATION COMMISSION

Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Ralph B. McLaughlin (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph B. McLaughlin

(Address) _____

SUBSCRIBED AND SWORN TO before me this 31st day of July, 19 56

Donna L. Riley
Donna L. Riley Notary Public.

My commission expires December 31, 1958

PLUGGING
FILE SEC. 30 T. 16 R. 11W
BOOK PAGE 83 LINE 27

15-009-03134-0000

BRUNSON DRILLING COMPANY, INC.
WICHITA, KANSAS

Well: Krier A # 8

Commenced RD 8-17-54
Completed RD 8-25-54

C.W.L. SE SE
Sec. 30-16-11
Barton County

Elevation: 1923 RB

Casing 381' 8 5/8" OD 24# rhd thd
3263' 5 1/2" OD #8 rd thd

Contractor: Pam-Kar Drilling Co.

Total Depth: 3264'

175 Ash cement
100 Ash cement

STRATA	DEPTH		TOPS
Surface, Soil & Clay	40	Heebner	2924-1001
Shale	210	Toronto	2942
Shale & Streaks of Sand	265	Douglas Sand	2971
Shale	381	Brown Lime	3021
Red Bed & Shale	710	Lansing	3041-1118
Anhydrite	790	quartz	3254-1331
Shale & Shells	870		
Shale	915		
Salt & Shale	1020	Total Depth	3264
Shale	1475		
Broken Lime	1545		
Shale & Lime	2365		
Shale & Shells	2705		
Shale & Lime	2785		
Lime & Shale	2925		
Lime, Shale & Sand	3012		
Lime & Shale	3254		
Quartz	3264		
Total Depth	3264		

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

PAM-KAR DRILLING COMPANY, INC.
BY

Ralph B. McLaughlin
Ralph B. McLaughlin-Sec. Treas.

Signed and sworn to in my presence this 2nd day of September, 1954, by Ralph B. McLaughlin, Secretary-Treasurer of the Pam-Kar Drilling Company, Inc. a corporation in the state of Kansas.

[Signature]
Notary Public

My commission expires September 4, 1957.

PLUGGING
FILE SEC 30 T 16 R 11W
BOOK PAGE 83 LINE 27