


FEB 14 1961

## WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barton County, Sec. 30 Twp. 16 Rge. 11 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE  
Lease Owner Independent Lease Management  
Lease Name Krier "A" Well No. 7  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 2-1-61 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 2-7-61 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3340 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	478'	None
				5-1/2"	3335'	2614'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3340', sanded from 3340' to 2970' and dumped 5 sacks of cement @ 2970'. Pulled 5 1/2" casing. Set 10' rock bridge from 320' to 310' and ran 30 sacks of cement. Mudded to 30', set 10' rock bridge to 20' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

3-30-61  
RECEIVED  
STATE CORPORATION COMMISSION

FEB 30 1961  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Knight Casing Pulling Co.  
Address Chase, Kansas

STATE OF Kansas COUNTY OF Rice, ss.  
Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of February, 1961

My commission expires May 20, 1964

Notary Public.



## BRUNSON DRILLING COMPANY, INC.

Well: Krier A #7

SE SE SE  
Sec. 30-16-11W  
Barton County, KansasCommenced RD: 6-12-53  
Completed RD: 6-23-53Elevation: 1912 KB  
Contractor: Pam-Kar Drlg.  
Co., Inc.Casing: 478' 10 3/4" O.D. 40#  
3335' 5 1/2" O.D. 14# 8rd thd.

STRATA	DEPTH	TOPS
Surface	42	Heebner 2941 - 1029
Sand, gravel, Shells	140	Toronto 2957 - 1045
Shale & Shells	240	Douglas 2988 - 1076
Sand	290	BR LM 3037 - 1125
Sand & Shale	400	Lansing 3057 - 1145
Shale & Shells	490	Cong. 3319 - 1407
Red Bed & Shale	745	Gorham 3333 - 1421
Chalk	749	
Anhydrite	760	
Red Beds & Shale	880	
Shale & Shells	1045	
Salt & Shale	1195	
Shale & Shells	1245	
Broken Lime	1560	
Lime & Shale	1805	
Broken Lime	1955	
Shale & Lime	2155	
Lime & Shale	2305	
Shale & Lime	2700	
Lime & Shale	2750	
Sand, lime, shale	3070	
Lime & Shale	3335	
Total Depth	3335	

RECEIVED  
STATE OF KANSAS COMMISSIONCONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

PAM-KAR DRILLING COMPANY, INC.  
BYRalph B. McLaughlin  
Ralph B. McLaughlin, Sec.

Signed and sworn to in my presence this 26th day of August, 1953 by Ralph B. McLaughlin, Secretary of the Pam-Kar Drilling Company, Inc., a corporation in the State of Kansas.

Dwight J. Stewart  
Notary Public

My commission expires January 6, 1954.