

15.083.10081.00.00

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Hodgeman County, Sec. 26 Twp. 21S Rge. (E)25 (W)

Location as "NE/CNW/SW" or footage from lines C SE NW

Lease Owner Hudson Petroleum Company

Lease Name Lee Well No. 7

Office Address P.O. Box 333, 4720 Rainbow, Kansas City, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 19

Application for plugging filed October 15 1964

Application for plugging approved 19

Plugging commenced October 16 1964

Plugging completed October 24 1964

Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott

Producing formation Depth to top Bottom Total Depth of Well 4556 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	453'	8 5/8"	453'	none
		0	4510'	5 1/2"	4510'	3062.26

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed plug to 4500', set 10' rock bridge and dumped 10 sacks of cement.
Bailed hole down to 460' and dumped 35 sacks of cement. Filled hole with mud from 360' to 45' and dumped 15 sacks of cement.
Hole plugged 2 p.m.

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1964 10-30-1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pipe Pullers, Inc.
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Dean Wells

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jean Keller
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of October, 1964

[Signature] Notary Public.

My commission expires July 7, 1968

15.083-10081.00.00
SHOLOM DRILLING COMPANY, INC.
6045 Pine Tree Drive
Miami Beach, Florida
33140

COMPANY: Hudson Petroleum Company
FARM: #7 LEE
LOCATION: SE NW Sec 26 T 21S R 25W., Hodgeman County, Kansas
ROTARY DRILLING CONTRACTOR: Sholom Drilling Co., Inc.

COMMENCED: 6/6/64
COMPLETED: 6/20/64 Rotary
I. P: Pending

Rotary T.D. 4552'

Casing Record:

8 5/8 @ 453' w/275 sax
5 1/2 @ 4510 w/75 sax

Drill Stem Tests:

#1 4512-4552. Rec. 135' muddy
oil. ISIP 1110, FSIP 1110
IFP-55, FFP 135#

Test rerun, tool plugged.

L O G

0 - 60 Clay & sand
60 - 453 Shale
453 - 535 Shale & sand
535 - 690 Shale
690 - 750 Sand & shale
750 - 1115 Red bed, shale & shells
1115 - 1335 Sand
1335 - 1390 Shale & shells
1390 - 1645 (Red bed) Shale & shells
1645 - 1660 Anhydrite
1660 - 2040 Shale & shells
2040 - 2480 Shale & Lime
2480 - 2735 Lime & shale
2735 - 3240 Lime
3240 - 3655 Lime & shale
3655 - 3665 Shale & lime
3665 - 4520 Lime
4520 - 4552 Lime
4552 T.D.


RECEIVED
STATE CORPORATION COMMISSION

OCT 30 1964


CONSERVATION DIVISION
Wichita, Kansas

STATE OF FLORIDA)
) ss.
COUNTY OF DADE)

I, Joseph Teichman, President of Sholom Drilling Company, Inc., a corporation of the State of Oklahoma, domesticated in the State of Kansas, being first duly sworn under oath, says: That I have knowledge of the facts, statements, and matters herein contained of the above described well as filed and that the same are true and correct.


Joseph Teichman

Subscribed and sworn to before me this 29th day of June, 1964


Notary Public

NOTARY PUBLIC STATE of FLORIDA at LARGE
MY COMMISSION EXPIRES JUNE 9, 1968
BONDED THROUGH FRED W. DIESTELHORST