


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County, Sec. 24 Twp. 21 Rge. (E) 25 (W)

Location as "NE/CNW/SE" or footage from lines. C SW/4 SW/4
Lease Owner Hudson Petroleum Co.
Lease Name Stoskoff Well No. 1
Office Address Box 333 Kansas City 3, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 3/19 1964
Application for plugging filed 3/19 1964
Application for plugging approved 3/19 1964
Plugging commenced 3/19 12:30 P 1964
Plugging completed 3/19 7:00 P.M. 1964
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Mr. Hugh Scott
Producing formation Dry hole Depth to top Bottom Total Depth of Well 4515 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	Barren	4484	4515	8 5/8	574'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 700'
Plug 25 sax cement at 700'
Mud to 500'
Plug 25 sax cement at 500'
Mud to 45'
Plug w/hulls & 15 sax cement at 45'

All cement plugs pumped by Sun Cementing Co., Truck.

RECEIVED
STATE CORPORATION COMMISSION

MAR 30 1964

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Rotary Hole (Additional description is necessary, use BACK of this sheet)
Address

STATE OF Florida, COUNTY OF Dade, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Joseph ...
6045 Pine Tree Drive, Miami Beach, Fla.
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of March, 1964

NOTARY PUBLIC STATE OF FLORIDA at LARGE
MY COMMISSION EXPIRES JAN. 26, 1968
BONDED THROUGH FRED W. DIESTELHORST

Ernest Neubauer
Notary Public.

My commission expires

15.083.10082.00.00

SHOLOM DRILLING COMPANY INCORPORATED
6045 Pine Tree Drive
Miami Beach, Florida 33140

COMPANY: Hudson Petroleum Co.
FARM: #1 Stoskoff
LOCATION: C SW SW Sec 24 T 21S R 25W Hodgeman County, Kansas
CONTRACTOR: Sholom Drilling Company, Inc.

COMMENCED: 3/8/64
COMPLETED: 3/19/64
I.P. : D & A

Elevation: 2384 K.B.
Rotary T.D: 4515'

Casing Record
8.5/8 @ 574' w/600 sax

DST 4495-4515
1 hr Rec 50' mud

LOG

- 0 - 70 Surface clay
- 70 @ 730 Shale, shells, sand
- 730 - 965 Red bed
- 965 - 990 Gyp and shale
- 990 - 1020 Gyp
- 1020 - 1086 Red bed and shale
- 1086 - 1290 Sand
- 1290 - 1425 Shale and shells
- 1425 - 1603 Red bed and shells
- 1603 - 1646 Anhydrite
- 1646 - 2275 Shale and shells
- 2275 - 2645 Shale and lime
- 2645 - 3075 Lime
- 3075 - 3885 Lime and shale
- 3885 - 4465 Lime
- 4465 - 4484 Lime and chert
- 4484 - 4509 Coring
- 4509 - 4515 Coring

RECEIVED
STATE CORPORATION COMMISSION

MAR 30 1964


CONSERVATION DIVISION
Wichita, Kansas

STATE OF FLORIDA)
) ss.
COUNTY OF DADE)

I, Joseph Teichman, President of Sholom Drilling Company, Inc.,
a corporation of the State of Oklahoma, domesticated in the State of Kansas,
being first duly sworn under oath, says: That I have knowledge of the facts
statements, and matters herein contained of the above described well as
filled and that the same are true and correct.


Joseph Teichman

Subscribed and sworn to before me this 25th day of March, 1964


Curran Newbauer
Notary Public

NOTARY PUBLIC STATE OF FLORIDA at LARGE
MY COMMISSION EXPIRES JAN. 26, 1968
BONDED THROUGH FRED W. DIESTELHORST

My commission expires: