

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER Comp. 6-9-63 (of this well) 2/88  
(This must be listed; if no API# was issued, please note drilling completion date.)

OPERATOR Phillips Petroleum Co. OPERATORS LICENSE NO. 5229

ADDRESS Route #3, Box 20-A, Great Bend, KS 67530 PHONE # (316) 793-8421

SECTION (FARM) Billings 'B' WELL NO. 1. WELL LOCATION C NE NE COUNTY Hodgeman

SEC. 35 TWP. 22S RGE. 23 ~~(S)~~ or (W) TOTAL DEPTH 4500 PLUG BACK TO 4500

Check One:

WELL X GAS WELL \_\_\_\_\_ D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8 SET AT 250 CEMENTED WITH 185 SACKS

CASING SIZE 5 1/2 SET AT 4493 CEMENTED WITH 100 SACKS

PERFORATED AT Open hole 4493-4500'

CONDITION OF WELL: GOOD \_\_\_\_\_ POOR \_\_\_\_\_ CASING LEAK X JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set 5 1/2" CIBP at ± 4450' and dump

2 SX cement with bailer on top of plug. Perforate casing at 850' with squeeze

gun. Pump 200 SX cement down casing through perfs & up backside to surface.

(If additional space is needed use back of form)

Fill backside of 8 5/8" casing.

WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: 9-1-87

G. L. Kelso PHONE # (316) 793-8421

ADDRESS Route 3, Box 20-A., Great Bend, Ks. 67530

PLUGGING CONTRACTOR \_\_\_\_\_ LICENSE NO. SEP 1 1987

ADDRESS \_\_\_\_\_ PHONE # ( ) \_\_\_\_\_

AGREEMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: JL Kelso  
(Operator or Agent)

DATE: 31 Aug 87

①

# LANE WELLS



*Gamma Ray Section*

A DIVISION OF PRELUDER INDUSTRIES

15-083-10025-0000

FILE NO.	COMPANY BIRMINGHAM-BARTLETT DRILLING CO.	
RECEIVED STATE CORPORATION COM SEP 1 1987 CONSERVATION DIVISION Wichita, Kansas	WELL	BILLINGS <sup>"B"</sup> NO. 1
	FIELD	HANSTON
	COUNTY	HODGEMAN STATE KANSAS
LOCATION:	C NE NE	Other Services
SEC 35	TWP 28S	RGE 23W

Permanent Datum	5' ABOVE GROUND LEVEL	Elev.	KB
Log Measured from	SAME	5 Ft. Above Permanent Datum	DF
Drilling Measured from	KELLY BUSHING		GL

Date	6-12-63
Run No.	1 NW
Type Log	G/R-N/L-CEMO
Depth-Driller	4499.5
Depth-Logger	4500
Bottom Logged Interval	4499
Top Logged Interval	3450 SURF
Type Fluid in Hole	OIL
Salinity Ppm Cl.	
Density Lb./Gal.	
Level	
Max. Rec. Temp. Deg. F	
Opr. Rig Time	3 1/2 HRS.
Recorded By	BARLOW
Witnessed By	KEEVERT

Run No.	Bore Hole Record			Casing Record			
	Bit	From	To	Size	Wgt.	From	To
1	12 1/4	SURF	240	8 5/8	32	SURF	240
1	7 7/8	240	4493	5 1/2	14	SURF	4493

FOLD HERE



Mike Hayden  
 Keith R. Henley  
 Rich Kowalewski  
 Margalee Wright  
 Judith A. McConnell

Governor  
 Chairman  
 Commissioner  
 Commissioner  
 Executive Director

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 200 Colorado Derby Building  
 202 West 1st Street  
 WICHITA, KANSAS 67202-1286

THIS NOTICE

DEC 1 '87

September 1, 1987

EXPIRES

WELL PLUGGING NOTICE

Billings "B" #1  
 C NE NE  
 Sec. 35-22S-23W  
 Hodgeman County

Phillips Petroleum Company  
 Route 3, Box 20-A  
 Great Bend, KS 67530

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist  
 Director  
 State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760