

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-083-20578-0000 (of this well) 6/87
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Edmiston Oil Co., Inc. OPERATORS LICENSE NO. 5042

ADDRESS 1260 KSB Building, Wichita, Kansas 67202 PHONE # (316) 265-5241

LEASE (FARM) Hays "B" WELL NO. 2 WELL LOCATION W/2 NW NW COUNTY Hodgeman

SEC. 30 TWP. 22 RGE. 23 or TOTAL DEPTH 4626' PLUG BACK TD

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8-5/8" SET AT 320 CEMENTED WITH 185 SACKS

CASING SIZE 4-1/2" SET AT 4622 CEMENTED WITH 125 SACKS

PERFORATED AT 4622-26

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Sand off to 4600', plug w/25 sx
Shoot pipe at approximately 2500', pull pipe. Plug at 1614' with 50 sx.

Plug surface with 150 sx 60/40 poz mix.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No Log IS ACO-1 FILED? Attached
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN To be arranged

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Dale May PHONE # (316) 564-2639

ADDRESS Box 232 Great Bend, Kansas 67530

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050 6/87

ADDRESS Box 347 Chase, Kansas 67524 PHONE # (316) 938-2457

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jon M. Callen
(Operator or Agent)

DATE: 12/31/86



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

APR 5 '87

EXPIRES

January 5, 1987

WELL PLUGGING NOTICE

Hays "B" #2
W/2 NW NW
Sec. 30-22S-23W
Hodgeman County

Edmiston Oil Company, Inc.
1260 KSB Bldg.
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Jack McCord, Director

Please contact the district office to review your suggested method of plugging
DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760
five days prior to plugging the well (KAR-82-3-113).