

15.083.20138.00.01

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217*Intentional or Authority to
Plug this Well was given
July 24, 1974.*RECEIVED
STATE CORPORATION COMMISSION

DEC 13 1974

CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Thunderbird Drilling, Inc.Complete Address Box 18407, Wichita, Kans.Lease Name Campbell Well No. # 1Location SW. N.W. Sec. 9 Twp. 22 Rge. (E) (W) 23County Hodgeman Total Depth 4644Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated Plugging Contractor Knight Casing PullingAddress Box 405, Chase, Kans 67524 License No. 436Operation Completed: Hour 3:30 PM Day 10th Month Dec Year 1974

The above well was plugged as follows:

Unknown how many feet of 7 7/8" casing.
Filled with sand to 4636 ft. 5 Sacks of Cement
on perforations from 4636-4600 ft. mix 4 Sacks
Cotton seed Hulls & Ten Sacks of Gell 50-Sacks
of Cement from 900-775. 5 1/2" casing. 4 Sacks of
Gell 1 Sack Cotton seed Hulls. 35 Sacks Cement
from 550-449. 5 Sacks Gell 1 Sack Cotton
seed Hulls. To 45 ft. 15 Sacks Cement from

I hereby certify that the above well was plugged as herein stated.

45-0. This was accomplished
by added Cement from
Great Bend, Kans.

Signed: Charles J. Thomas

Well Plugging Supervisor

INVOICED

DATE 12/16/74INV NO. 479-W