

15.083.10326.00.00

Form CP-3
Rev. 6-26-62

MP
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

DEC 16 1963

CONSERVATION DIVISION
Wichita, Kansas

12-16-1963

Operator's Full Name Donald C. Slawson

Complete Address: 408 One Twenty Bldg., Wichita, Kansas

Lease Name Lee "A" Well No. # 1

Location C NW NW Sec. 14 Twp. 22 Rge. 23 (E) (W)W

County Hodgeman Total Depth 4685

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Murfin Drilling Co.

Address: 617 Union Center, Wichita, Kansas License No. _____

Operation Completed: Hour 6:00AM Day 14th Month December Year 1963

The Above well was plugged as follows:

329' of 8 5/8" surface pipe, cemented with 175 sacks. Fluid was up in
hole. 1st cementing plug and 1/2 sack hulls was pushed to 700', cemented
with 25 sacks, through drill pipe. 2nd cementing plug and 1/2 sack hulls
was pushed to 300', cemented with 25 sacks, through drill pipe. Hole
was filled with drilling mud to 40', 3rd cementing plug, bridged with
hulls, cemented with 10 sacks to base cellar. Rat hole bridged and cement-
ed with 2 sacks. The cementing of plugs was done by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/17/63

INV. NO. 8289-u