

15.083.10027.00.00

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 19 1965  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Birmingham-Bartlett Drilling Co.

Complete Address: 300 Kaufman Bldg. Wichita, Kansas

Lease Name Jensen Well No. # 1

Location SE SE Sec. 26 Twp. 22 Rge. 23 (W)

County Hodgeman Total Depth 4509'

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Co.

Address: Great Bend, Kansas License No. # 2

Operation Completed: Hour 4 PM Day 16 Month 4 Year 65

The Above well was plugged as follows:

8 5/8"-240' Circulated w/cement. 5 1/2"-4504' Cemented.

Plug bottom w/5 Sax.cement top cement 4450' Mud 4450' to 700'

Spotted 25 Sax.cement 700' to 625' Mud 625' to 250'

Spotted 25 Sax.cement 250' to 175' Mud 175' to 45'

Plug, Hulls, 15 Sax.cement 45' to 0 Pulled 3450' 5 1/2" pipe.

Company Pump. Cut surface off 5' below ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 4/19/65  
INV. NO. 1005-W

Signed [Signature]  
Well Plugging Supervisor