

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 65-4

LOCATION NE 77E-SE

SEC. 20 TWP. 16 RGE. 11-W

*Call Prod*

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 4 Lease Kreier "A"

Operator Brunson Drilling Co, Inc Address 333 First Natl Bldg- Wichita-Kans

Field \_\_\_\_\_ County Barton

Total Depth 3223 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 702 ft. not cemented  
5" casing set at 3220 ft - 50 sacks of cement  
Plugged back to 3009 ft. filled hole with sand to 2950 ft  
blended 5 sacks of cement at 2950 ft - shot off & pulled  
the 5" casing - filled hole with sand - shot off & pulled 600 ft  
of 10 3/4 casing - set rock bridge & 40 sacks of cement  
at 250 ft. mud to 30 ft. bridge & 10 sacks cement at the surface.  
The West Supply Co - Plugging Contractors

**PLUGGING**  
FILE SEC 307-66-14  
BOOK PAGE 65 LINE 4

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 9 - 1953  
CONSERVATION DIVISION  
Wichita, Kansas

C. M. Stough  
District Conservation Agent  
Date 1-7-53

1-9-53