

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT 15-075-20357-000

API Number 15-075 20, 257 Authority July 13, 1981

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name Woolsey Petroleum Corporation

Complete Address 300 W. Douglas #400, Wichita Kans.

Lease Name O. Brate Well No. 1

Location C. NE. SE. Sec. 22 Twp. 21 Rge. 39 (East) (West)

County Hamilton Total Depth 6100

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated

Plugging Contractor Midwest casing pulling

Address Sublette Kans. License No. \_\_\_\_\_

Operation Completed: Hour: 3:00 PM Day: 4 Month: Aug Year: 1981

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

There was 802' of 8 1/2" surface casing  
4 1/2" was set to 2951'. Plug back was  
2781'. Perforations were 2780-2767. 1st  
plug on bottom with 2 1/2" bulbs & 20  
lbs cement. 2nd plug cover @ keyline  
from 1130-930 with 80 lbs cement.  
Rubber plug at 775'. 3rd plug at 775'  
with 35 lbs cement. 4th plug at 100-0  
with 35 lbs cement. There was 2270

I hereby certify that the above well was plugged as herein stated.

of 4 1/2" salvaged. **INVOICED** **RECEIVED**  
STATE CORPORATION COMMISSION  
Signed: W. Thomas  
Conservation Division Agent

DATE 9-25-81

AUG 6 1981  
08-06-81  
CONSERVATION DIVISION  
Wichita Kansas

INV. NO. 7463W

DRILLER'S LOG

WOOLSEY PETROLEUM CORPORATION  
No. 1 O'Brate  
C NE SW Section 22 - 21S - 39W  
Hamilton County, Kansas

Commenced: 3/13/81  
Completed: 4/05/81

Surface Casing: 801' of 8-5/8"  
Cmtd w/300 sx Hal.light, 2% cc,  
fol w/ 150 sx Class H, 3% cc.

FORMATION

DEPTH

|                          |                 |
|--------------------------|-----------------|
| Surface Hole             | 0 - 815         |
| Shale & Sand             | 815 - 1178      |
| Sand & Shale             | 1178 - 1572     |
| Shale                    | 1572 - 3305     |
| Shale & Lime             | 3305 - 3420     |
| Shale                    | 3420 - 4135     |
| Lime                     | 4135 - 4360     |
| Lime & Shale             | 4360 - 4475     |
| Shale & Lime             | 4475 - 4537     |
| Lime & Shale             | 4537 - 4600     |
| Shale & Lime             | 4600 - 4675     |
| Lime & Shale             | 4675 - 4860     |
| Lime                     | 4860 - 4955     |
| Lime & Morrow Shale      | 4955 - 5080     |
| Shale                    | 5080 - 5270     |
| Mississippi              | 5270 - 5645     |
| Mississippi & Kinderhook | 5645 - 5830     |
| Viola                    | 5830 - 5910     |
| Viola - Arbuckle         | 5910 - 6075     |
| Arbuckle                 | 6075 - 6100 RTD |

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

CHEYENNE DRILLING, INC.

*A. J. Jacques*  
A. J. Jacques  
RECEIVED  
STATE CORPORATION COMMISSION  
JUL - 1 1981

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 13th day of April, 1981.

My Commission Expires:  
March 18, 1985

CONSERVATION DIVISION  
Wichita, Kansas

*Sharyn K. Shearmire*

Sharyn K. Shearmire, Notary Public

