

KANSAS

*Y* STATE CORPORATION COMMISSION

15-075-10060-0000

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 20 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Lvo Corporation

Complete Address Box 2848, Tulsa, Oklahoma 74101

Lease Name Unit 1711 Well No. 1

Location C NW SE Sec. 17 Twp. 21 Rge. 41 (E) (W)

County Hamilton Total Depth 2800'

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Sargents Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 3:00PM Day 10 Month 9 Year 1971

The above well was plugged as follows:

8 5/8" to 121' circulated w/ cement. 4 1/2" to 2793' cemented.

Top perforations 2750' Plug bottom w/ 20 sacks cement.

Top of cement 2616' Mud 2616' to 600'

Spotted 35 sacks cement 600' to 500' Mud 500' to 150'

Spotted 10 sacks cement 150' to 50' Mud 50' to 45'

Plug, Halls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2252' of 4 1/2" casing

I hereby certify that the above well was plugged as herein stated:

INVOICED

Signed: *Edward J. Eves*  
Well Plugging Supervisor

DATE 9-22-71

INV. NO. 4352-W