

*4*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

15-075-10024-0000

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 23 1967  
02-23-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Livingston Oil Company

Complete Address: Box 1797, Tulsa, Oklahoma

Lease Name Unit 2311 Well No. 2311

Location C SE NW Sec. 23 Twp. 21 Rge. 41 (X) (W)

County Hamilton Total Depth 2810'

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 4:30PM Day 20 Month 2 Year 1967

The Above well was plugged as follows:

8 5/8" to 174' circulated w/ cement. 4 1/2" to 2804' cemented

Top Perforations 2782' Plug bottom w/ 15 sacks cement

Top of cement 2600' Mud 2600' to 600'

Spotted 25 sacks cement 600' to 525' Mud 525' to 175'

Spotted 15 sacks cement 175' to 130' Mud 130' to 40'

Plug, Halls & 10 sacks cement 40' to 0' Company Pump

Pulled 2508' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edna E. Ewing  
Well Plugging Supervisor

DATE 2/23/67  
INV. NO. 4806-W